

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Strike out upper line
when reporting plug-
ging of formations.

Stanton County, Sec. 25 Twp. 29S Rge. 43W (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C NW SW
Lease Owner Ashland Oil & Refining Company
Lease Name Burnett Well No. 1-25
Office Address Box 9695, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 21 19 59
Application for plugging filed September 17 19 59
Application for plugging approved 19
Plugging commenced September 18 19 59
Plugging completed September 19 19 59
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production Dry 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes, permission by Mr. Lewis Broch

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation None - Dry Depth to top - Bottom - Total Depth of Well 5564 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lansing	salt water	3922	3947	13 3/8	203'	- None -
Marmaton	salt water	4718	4750	8 5/8	1620'	1027'
Keyes sand	salt water	5488	5500			
		85510	5540			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

This well was drilled to total depth of 5564'. 8 5/8" csg. was set @ 1620', cemented with 125 sks.

This pipe shot off & pulled @ 1027' - recovered 1027' - Hole was filled with mud. A cement plug was set from 675' to 585' with 90 sks. as per request of Mr. M. A. Rives. Cement plug was set by HOWCO.

Placed cement plug @ surface with 10 sks.

Casing was pulled by Toland & Reeves, Oklahoma City, Oklahoma

13 3/8" surface pipe was set @ 203' - this pipe was not pulled, and cement was circulated from 203' to surface.

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1959

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Wichita, Kansas

Correspondence regarding this well should be addressed to Mr. Jack F. Precise, Div. Prod. Supt.
Address Box 9695, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
I, Jack F. Precise (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack F. Precise
Box 9695, Oklahoma City, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of October, 1959

My Commission Expires November 26, 1959

Peggy O'Haughey Notary Public.

15-187-00009-0000

Burnett Unit No. 1-25
C NW SW, Sec. 25-T29B-R43W
Stanton County, Kansas

Calvert Drilling Company
Started July 26, 1959 - Completed 8-19-59

Sand & Clay	0	218
Sand, Clay, Shale	218	1613
Shale	1613	2030
Lime & Shale	2030	2062
Lime & shale	2062	2928
Shale	2928	3318
Lime & Shale	3318	3560
Lime & Shale	3560	3760
Lime	3760	3931
Lime & Shale	3931	4081
Lime & Shale	4081	4276
Lime	4276	4480
Lime & Shale	4480	4677
Lime	4677	4724
Lime	4724	4832
Lime & Shale	4832	4985
Lime & Shale	4985	5198
Lime & Shale	5198	5410
Lime & Shale	5410	5536
Lime & Shale	5536	5564
		Total Depth

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1962

CONSERVATION DIVISION
Wichita, Kansas

I, the undersigned, swear the information disclosed hereon to be true and correct.

Signature: R. E. Calvert

SUBSCRIBED AND SWORN TO BEFORE ME THIS 19th DAY OF Sept. 1962

MY COMMISSION EXPIRES 3-8-66

Jane La Rue Whitfield
Notary Public