

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stanton

County. Sec 16 Twp 29S Rge 43W (E) W (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines C-NE/4

Lease Owner The Superior Oil Company

Lease Name Burnett Unit Well No. 1

Office Address Box 690, Chickasha, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 13, 1956

Application for plugging filed October 13, 1956

Application for plugging approved October 13, 1956

Plugging commenced October 13, 1956

Plugging completed October 13, 1956

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 5559 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Elmont	Barren	3216		10-3/4"	1602 Ft.	None
Topeka	Barren	3374				
Morrow	Salt water	5391				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from...feet to...feet for each plug set.

- Placed 100 sack cement plug at 5557.
- Placed 90 sack cement and 10 sacks sand at 3800 ft.
- Placed 125 sack cement plug at 3400 ft.
- Placed 35 sack cement plug at 650 ft. on top of wooden plug driven to 650 ft.
- Placed 15 sack cement plug at surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Superior Oil Company  
Address Box 690, Chickasha, Oklahoma

STATE OF Oklahoma, COUNTY OF Grady, SS.

Wm. N. Mosley, District Engineer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wm. N. Mosley

Box 690, Chickasha, Oklahoma (Address)

SUBSCRIBED AND SWORN to before me this 17th day of October, 1956

My commission expires 9-15-60

M. F. Frigel Notary Public.

23-3273-s 4-50-10M STATE CORPORATION COMMISSION

PLUGGING  
FILE SEC 16 T 29 R 43W  
BOOK PAGE 108 LINE 11

OCT 13 1956  
10-18-1956  
CONSERVATION DIVISION  
Wichita, Kansas

## Superior Oil Co.

BURNETT UNIT #1C-NE- $\frac{1}{4}$ -Section 16-29S-43WWELL LOG

Figures below indicate top of the formations.

Sand and shale	0-106
Sand, shale, shells	600
Shale, red beds, sd	794
Red beds and shale	1133
Sand and shale	1378
Shale and gypsum	1425
Anhydrite and shale	1514
Red beds	1890
Red beds and sand	2275
Lime, shale, sand	2535
Lime and shale	2650
Lime	3425
Lime and shale	3512
Lime	3980
Lime and shale	4582
Lime	4735
Lime and shale	4825
Shaly sand	5430
Shale and sand	5459
Sand	5483
Sand and shale	5520
Shale and lime	5559
T.D.	5559

(DRY AND ABANDONED)

PLUGGING	
FILE SEC	16 T. 29 R. 43W
BOOK PAGE	108 LINE 11

**RECEIVED**  
STATE CORPORATION COMMISSION  
OCT 17 1956  
CONSERVATION DIVISION  
Wichita, Kansas