


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67317

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Stanton County, Sec. 12 Twp. 29 Rge. 43 (E) (W)
Location as "NE/CNW&SW" or footage from lines. C NE/4 NW/4
Lease Owner S. Keith Tuthill and Bill J. Barbee
Lease Name Cockrum Well No. #1-12
Office Address 211 Vaughn Bldg., Amarillo, TX 79101
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed June 30, 1975
Application for plugging filed 1975
Application for plugging approved June 30, 1975
Plugging commenced June 30, 1975
Plugging completed June 30, 1975
Reason for abandonment of well or producing formation all zones are waterbearing
If a producing well is abandoned, date of last production 1975
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5750' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
All porous zones in well are wet	RECEIVED STATE CORPORATION COMMISSION			8 5/8"	1537'	0
	JUL 9 1975					
	CONSERVATION DIVISION Wichita, Kansas					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Report of Leo F. Massey: "RTD 5750' 8 5/8" casing set 1573' cwc Plg. Mat. Cem. Gunned pits, circulated heavy mud, set 100 sk cement plug at 2800' thru drill pipe. Heavy mud to 1000' set 25 sk cmt plug thru drill pipe. Heavy mud to 30' set solid bridge & 15 sk cmt plug to base of cellar."

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Services
Address Liberal, Kansas

STATE OF TEXAS COUNTY OF POTTER
S. Keith Tuthill (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. Keith Tuthill
211 Vaughn Bldg., Amarillo, TX 79101 (Address)

SUBSCRIBED AND SWORN to before me this 7th day of July 1975
My commission expires 6/1/75
Becky S. Hatfield Notary Public



RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1975
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

COCKRUM NO. 1

CASING RECORD:	OPERATOR: Tuthill & Barbee	DESCRIPTION:
8-5/8" set @ 1537' w/700 sax cement	CONTRACTOR: Sage Drilling Co.	C NE NW Sec. 12-29S-43W Stanton County, Kansas.
TOTAL DEPTH: 5750'	COMMENCED: June 13, 1975	
	COMPLETED: June 30, 1975	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	80	
Shale & Sand	80	456	
Red Bed	456	860	
Red Bed w/Lime Streaks	860	1326	
Shale	1326	1561	
Shale & Lime	1561	2555	
Lime & Shale	2555	5260	
Shale & Lime	5260	5398	
Lime & Shale	5398	5680	
Shale	5680	5699	
Lime & Shale	5699	5750	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By *T. M. McCaul, Jr.*
T. M. McCaul, Jr.



Subscribed and sworn to before me this 7th day of July, 1975.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1978.

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1975
CONSERVATION DIVISION
Wichita, Kansas