

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-187-20813-0000

LEASE NAME Tiffany Jade

WELL NUMBER 1-35

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1000 Ft. from <sup>N</sup> Section Line  
2000 Ft. from E Section Line

LEASE OPERATOR Amoco Production Company

SEC. 35 TWP. 29S RGE. 40 (E) or (W)

ADDRESS PO Box 800 Room 924 Denver, CO 80201

COUNTY Stanton

PHONE# (303) 830-5323 OPERATORS LICENSE NO. 5952

Date Well Completed 3/26/96

Character of Well Shut in Oil Well

Plugging Commenced 6/10/96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/10/96

The plugging proposal was approved on 6-3-96 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation St. Louis Depth to Top 5616' Bottom 5630' T.D. 5750'  
but did not produce, just shut in.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8.625"	1573'	0
	Production			4.5"	5750'	1420'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Well was plugged using Premium Plus Lite with 6% gel. CIBP is already in well at 5575'. Find

freepoint at 3850'. Cut casing off at 3800'. Parted casing at 1420'. Pull 1420' of casing. Preforate at 2803', pump 220 sacks, leaving backside and casing full from 1400' to 2800'. Set 40 sack plug from 360' to 550'. Spot 10 sack plug from ground level to 60'. Cut casing off 5'

(If additional description is necessary, use BACK of this form.) KANSAS CORPORATION COMMISSION

below ground level and weld on identification cap.

Name of Plugging Contractor Halliburton License No. JUL 12 1996

Address \_\_\_\_\_

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Amoco Production Company 7-12-1996  
CONSERVATION DIVISION  
WICHITA, KS

STATE OF Colorado COUNTY OF Denver, ss.

Susan R. Potts (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Susan R. Potts

(Address) PO Box 800 Room 924 Denver, CO 80201

SUBSCRIBED AND SWORN TO before me this 11th day of July, 19 96

Diana L. Harris  
Notary Public

My Commission Expires: 11-10-96