


15-187-00072-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stanton County. Sec. 4 Twp. 29S Rge. 42 <sup>W</sup>~~W~~ (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE-SW-SE  
Lease Owner The Superior Oil Company  
Lease Name Tucker "A" Well No. 68-4  
Office Address Box 690, Chickasha, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 2, 1951 1951  
Application for plugging filed November 9, 1951 (Phone) 1951  
Application for plugging approved November 9, 1951  
Plugging commenced December 4, 1951  
Plugging completed December 6, 1951  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Phillippi, Liberal, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 6432 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation   | Content | From | To   | Size    | Put In | Pulled Out |
|-------------|---------|------|------|---------|--------|------------|
| Hugoton     | Dry     | 2315 | 2600 | 13-3/8" | 625    | -----      |
| Mississippi | Water   | 5422 |      | 9-5/8"  | 2653   | 1275       |
| Arbuckle    | Water   | 6369 |      |         |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

75 Sax Cement Plug From 6125 To 6385  
100 " 5700 To 5800  
50 " 5309 To 5441  
25 " 5385 To 3651  
25 " 3125 To 3190  
100 " 2425 To 2707  
50 " 2127 To 2137  
50 " 547 To 620  
10 " Surface To 12'

Pipe was cut off 4' below ground level. Hole is full of heavy mud between plugs.

REC  
STATE  
DEC 11 1951 12-11-1951  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to The Superior Oil Company  
Address Box 690, Chickasha, Oklahoma

STATE OF Kansas, COUNTY OF Stanton, ss.  
James K. Lawson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) James K. Lawson, Engineer  
Box 690, Chickasha, Oklahoma (Address)

SUBSCRIBED AND SWORN to before me this 10th day of December, 1951  
L. R. Stephens Notary Public.

My commission expires July 15, 1953 22-7377-8 4-49-10M

PLUGGING  
FILE SEC 4 T29 R424  
BOOK PAGE 130 LINE 33

# THE SUPERIOR OIL COMPANY

P. O. BOX 690

CHICKASHA, OKLAHOMA

TELEPHONE 3303

## WELL LOG:

TUCKER "A" 68-4 SE-SW-SE-SECTION 4, T29N R42W

| <u>TOP</u> | <u>BOTTOM</u> | <u>FORMATION</u>   |
|------------|---------------|--------------------|
| 0          | 405           | Sand and Gravel    |
| 405        | 1998          | Red Beds           |
| 1998       | 2163          | Red Beds and Shale |
| 2163       | 2416          | Lime and Shale     |
| 2416       | 2436          | Lime               |
| 2436       | 3185          | Lime and Shale     |
| 3185       | 3244          | Lime               |
| 3244       | 3368          | Lime and Shale     |
| 3368       | 3477          | Lime               |
| 3477       | 3624          | Lime and Shale     |
| 3624       | 3684          | Lime               |
| 3684       | 4133          | Lime and Shale     |
| 4133       | 4385          | Lime               |
| 4385       | 4449          | Lime and Shale     |
| 4449       | 4596          | Lime and Chert     |
| 4596       | 4960          | Lime               |
| 4960       | 5180          | Lime and Shale     |
| 5180       | 5257          | Shale and Sand     |
| 5257       | 5416          | Shale              |
| 5416       | 5426          | Lime and Shale     |
| 5426       | 5959          | Lime               |
| 5959       | 6130          | Sandy Lime         |
| 6130       | 6213          | Chert and Lime     |
| 6213       | 6249          | Lime and Sand      |
| 6249       | 6278          | Lime               |
| 6278       | 6438          | Dolomite           |

RECORDED  
 STATE OF OKLAHOMA  
 DEC 19 1951  
 COMMISSIONER OF GEOLOGY  
 WASHINGTON, D.C.

I, the undersigned, being first duly sworn upon oath, state that this well log is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

FILE SEC-4 T29 R42W  
 BOOK PAGE 130 LINE 33

*James K. Lawson*  
 James K. Lawson, Engineer

Subscribed and sworn to before me this 17th day of Dec., 1951

My Commission expires July 15, 1953. *L. R. Stephens*  
 Notary Public