


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
245 North Water  
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Stanton County, Sec. 31 Twp. 29 Rge. 41 (E) (W)  
Location as "NE/CNW/SW" or footage from line: Center of NW/4  
Lease Owner: B. D. Wilkerson  
Lease Name: B. D. Wilkerson Well No. 1  
Office Address:  
Character of Well (completed as Oil, Gas or Dry Hole): dry hole  
Date well completed: February 24, 19 76  
Application for plugging filed: March 17, 19 76  
Application for plugging approved: March 18, 19 76  
Plugging commenced: March 17, 19 76  
Plugging completed: March 17, 19 76  
Reason for abandonment of well or producing formation: non-commercial  
If a producing well is abandoned, date of last production: - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Clarence Thomas  
Producing formation: - Depth to top: - Bottom: - Total Depth of Well: 5500 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Topeka	saltwater	3505	3550	8-5/8"	1534'	-
Wabaunsee	saltwater	2852	2886 OA	5-1/2"	3034'	2192.85'
Wabaunsee	saltwater	2956	2962			
Council Grove	saltwater	2418	2498 OA			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Plugged with cast iron bridge plug @ 2300' with 2 sx cement on top of bridge plug.  
Spotted 50 sx cement plug 1500-1320' by pump and 15 sx plug from 40' to surface.

RECEIVED  
STATE OF KANSAS  
MAY 12 1976  
CONSERVATION DIVISION  
KANSAS  
WICHITA  
5-12-1976

Name of Plugging Contractor: Welex Corporation  
Address: Liberal, Kansas

STATE OF Texas COUNTY OF Potter ss.  
D. T. Stogner, Jr. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. T. Stogner, Jr.  
P. O. Box 12058, Amarillo, TX 79101  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of May 19 76

My commission expires June 1, 1977  
Donna Murdock Notary Public.

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

B. D. Wilkerson  
C-NW Sec 31-29S-41W  
Stanton County Kansas

Commenced: 2-7-76

Completed: 2-24-76

OPERATOR: CHEROKEE & PITTSBURG COAL & MINING CO.

Depth From	To	Formation	Remarks
0	61	Surface Clay-Sand	Ran 37 jts of 28# 8 5/8"
61	568	Sand-Clay	csg. set @ 1530' Cemented
568	730	Redbed-Sand-Anhy	w/600 sks Howco lite
730	1116	Redbed-Anhy	2% CC, + 150 sks Howco lite
1116	1210	Redbed-Gyp	3% CC PD @ 7:15 a.m. 2-9-76
1210	1337	Gloretta Sand	
1337	1660	Redbed	
1660	2121	Shale	
2121	2438	Shale-Redbed-Lime	
2438	5500	Lime-Shale	
	5500 - TD		Ran 71 jts of 5 1/2" csg set @ 3031' Cemented w/50 sks Class H 4% Gel 200 sks 50/50 Posmix w/18% Salt & 12 1/2% Gilsonite per sack PD @ 6:00 a.m. 2-24-76

MAR 22 1976

CONSERVATION DIVISION  
Wichita, Kansas

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled C-NW Sec 31-29S-41W, Stanton County, Kansas, to the best of my knowledge and belief.

*James S. Sutton II*  
JAMES S. SUTTON II

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State on this 3rd day of March 1976, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

*Elizabeth J. Edwards*  
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission Expires: February 6, 1979.

