

15-187-00063-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stanton County, Sec. 36 Twp. 29S Rge. 40 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE NW
Lease Owner Pan American Petroleum Corporation
Lease Name Dyche Gas Unit Well No. 1
Office Address Ulysses, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 4-10 19 62
Application for plugging filed 5-24 19 62
Application for plugging approved 6-1 19 62
Plugging commenced 6-6-62 19
Plugging completed 6-8-62 19
Reason for abandonment of well or producing formation Deposited No commercial quantities of oil or gas present.
If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Bill Lackamp
Producing formation none Depth to top _____ Bottom _____ Total Depth of Well 5800 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TOPS	SIZE	PUT IN	PULLED OUT
Council Grove			2544	8-5/8"	1691'	None
Pennsylvanian			2966	4-1/2"	5480'	2223'
Missouri			3776			
Des Moines			4384			
Chester			5434			
St. Louis			5640			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to plug back @ 3460', sanded to 2950' and dumped 2 sacks of cement @ 2950' with dump bailer. Pulled 4 1/2" casing to 650' and pumped in 30 sacks of cement @ 650'. Pulled balanced of 4 1/2" casing, checked hole to 370', mudded to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar. Cut off 8-5/8" 4" below ground level and welded on cap.

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1962
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

6-19-1962

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of June, 1962

My commission expires May 20, 1964
Milton J. Volin Notary Public.

FORMATION RECORD

DESCRIBE EACH FORMATION DRILLED. INDICATE THICKNESS, CONTENT AND WHETHER DRY, OR OIL, GAS, OR WATER BEARING.

FORMATION	TOP	BOTTOM	FORMATION	TOP	BOTTOM
Sand-clay	0	550			
Redbed	550	740			
Redbed-sand	740	1440			
Redbed	1440	1520			
Anhy	1520	1667			
Anhy-shale	1667	1946			
Shale	1946	2099			
Shale-lime	2099	3317			
Lime	3317	4555			
Lime-chert	4555	4615			
Lime	4615	4825			
Lime-shale	4825	4905			
Lime	4905	5910			
Lime-shale	5910	5527			
Lime	5527	5800			
Total Depth	5800				
EB depth	3460				