


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stanton County, Sec. 97 Twp. 29S Rge. (E) 42 (W)
Location as "NE/CNWxSWx" or footage from lines NE NW NE
Lease Owner Mallonee-Mahoney, Inc.
Lease Name Tucker Well No. 1
Office Address 925 Sutton Place, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-23 19 69
Application for plugging filed 2-24 19 69
Application for plugging approved 2-24 19 69
Plugging commenced 2-24 19 69
Plugging completed 7 P.M. 2-24 19 69
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eyes
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5,560' KB Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud 5,560' to 800'; 35 sx Common Cement by Halliburton 800' to 700'.
Heavy Mud 700' to 45'; Rubber Plug, 15 sx Common Cement 45' to 0.

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Service Drilling Company
Address Tulsa, Oklahoma

STATE OF Kansas COUNTY OF Seward, ss.
I, William F. Dean (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William F. Dean
Box 1257, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of February, 1969

My commission expires January 31, 1971

Jolanda Abbott
Notary Public.



SEC. 9-29-42W
NE NW NE

MALLONEE-MAHONEY, INC.

TUCKER NO. 1 WELL
Stanton County, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 24 1969
CONSERVATION DIVISION
Wichita, Kansas

COMMENCED OPERATIONS: 1-31-69

COMPLETED OPERATIONS: 2-24-69

DRILLERS LOG

1-31-69	0 - 90	Sand.
2-1-69	90 - 1126	Surface Sand, Red Bed, Stks Gypsum & Shale.
2-2-69	1126 - 1565	Gypsum, Anhydrite and Sand.
2-3-69	1565 - 2390	Anhydrite & Shale.
2-4-69	2390 - 2927	Shale w/Stks chalklime, Anhydrite & Lime.
2-5-69	2927 - 3415	Chalklime, Shale & Gypsum.
2-6-69	3415 - 3700	Lime & Shale.
2-7-69	3700 - 4035	Lime, Shale & Sand.
2-8-69	4035 - 4274	Lime and Shale.
2-9-69	4274 - 4386	Lime.
2-10-69	4386 - 4495	Lime, Broken Lime & Shale.
2-13-69	4495 - 4554	Lime & Shale.
2-14-69	4554 - 4711	Lime and Shale.
2-15-69	4711 - 4772	Dry Drill.
2-19-69	4772 - 4883	Lime.
2-20-69	4883 - 5003	Lime & Shale.
2-21-69	5003 - 5125	Lime & Shale.
2-22-69	5125 - 5451	Lime & Shale.
2-23-69	5451 - 5560	Lime & Shale.

CASING RECORD

2-2-69 Ran 39 Jts. 1566' of 8 5/8" 23# Foster Casing.
Set at 1565. Cemented with 600 sacks pozmix, 4% Gel.
and 2% c.c. and 200 sacks common, 3% c.c.

2-24-69 Plugged with:
35 sacks @ 800'
15 sacks from 45' to top.

THE UNDERSIGNED, F. W. MALLONEE, HEREBY CERTIFIES THAT THE ABOVE IS A TRUE AND CORRECT LOG OF THE FORMATIONS ENCOUNTERED IN DRILLING THIS WELL IN ACCORDANCE WITH THE DAILY DRILLING REPORTS.

F. W. Mallonee
F. W. Mallonee

Subscribed and sworn to before me this
20th day of March, 1969.

Leola Lynskey
Leola Lynskey - Notary Public
My commission expires April 13, 1972

