


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 35 Twp. 29 Rge. 7W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Pickrell Drilling Company
Lease Name Insho-Jackson Well No. 1
Office Address 2820 Paseo Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19
Application for plugging filed July 19, 1962 19
Application for plugging approved July 20, 1962 19
Plugging commenced August 18, 1962 19
Plugging completed August 21, 1962 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman E. Justus
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4166 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	240	none
				5 1/2	none	3455

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cleaned out cellar, measured T.D. and sanded to 4100'. Dumped 5 sacks cement.
Rigged up and worked pipe. Shot @3800-3700-3600-3522'.
Worked pipe and shot @3490-3430'. Gas blew in and wekkilled the gas. Pulled pipe.
Pulled pipe and plugged well with mud and built rock bridge @200'. Filled hole and rock bridge and capped well with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casigg Pulling, Inc.
Address Box 221 Great Bend, Kansas

9-12-1962

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221 St. Bent, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of August, 1962

My commission expires July 23, 1966

Notary Public.

COMPANY: Pickrell Drilling Company
 705 Fourth National Bank Building
 Wichita 2, Kansas

8/13/59
 8/12/59

LOCATION: NE NE NW Sec. 35-29-7, Ki County, K
 #1 INSERO - JACKSON

CONTRACTOR: PICKRELL DRILLING COMPANY
 Wichita, Kansas

CASING RECORD:
 240' (9jts.) 8 5/8" 32# casing cemented with 100 sacks, 2% gel, cement circulated.
 136 jts. of O.D. 14# 8rd Sm. Republic casing (7/8") set at 4237' cemented with
 90 sacks, 2% gel.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Red Rock	209'	Circ. for samples:
Red Beds/ Green shale, and Gyp.	650'	
Blue Shale/ Anhydrite	813'	4115'
Lime and Shale	1095'	4125'
Shale and Shells	1380'	4135'
Lime and Shale	2795'	4155'
Shale and Sandy Lime	3125'	4165'
Shale, Lime and Sand	3300'	4200'
Lime and Shale	3448'	4230'
Lime	3480'	4230'
Lime and Shale	3642'	
Lime	3835'	
Lime and Shale	4110'	
Mississippi	4238'	
RTD	4238'	

Slip Test:

2000' 0°
 3000' 0°
 4000' 0°

S.L.M.

2000' O.K.
 3000' O.K.
 4000' O.K.

RECEIVED
 STATE CORPORATION COMMISSIONER
 COMMISSION DIVISION
 WICHITA, KANSAS

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts
 Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 14th day of August, 1959, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: October 15, 1962

Judith L. Palmer
 Notary Public