

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 58-42

LOCATION 150N-150E-85E

SEC 17 TWP 29<sup>S</sup> RGE 40<sup>W</sup>

Dry Hole  Abandoned Oil Well  Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease RAY

Operator KANSAS-NEBRASKA NAT. Address LAKIN Ks.

Field HUGOTON County STANTON

Total Depth 2354 Feet.

Plugging Contractor MILLER CASING PULLING Co. GT. BEND Ks.

Plugging Contractor's License No. \_\_\_\_\_

Address GT. BEND Ks.

(Describe briefly the manner in which the well was plugged)

8 5/8 SET AT 477' - 5 1/2 SET AT 2352 - 150  
SACKS CEMENT. TOP PERF. 2230'. FILLED WITH SAND  
TO 2230', DUMPED 5 SACKS CEMENT. TOP 2195'.  
SET ROCK BRIDGE AT 450', DUMPED 20 SACKS CEMENT  
TOP 385'. HEAVY MUD TO 50'. SET ROCK BRIDGE  
+ DUMPED 15 SACKS CEMENT. CUT PIPE  
OFF 4' BELOW SURFACE + CAPPED.

RECEIVED  
STATE CORPORATION COMMISSION

SEP - 4 1954 10-4-54

*Adrian Farr*  
District Conservation Agent

Date 8-28-54

PLUGGING  
FILE SEC 17 T 29 R 40  
BOOK PAGE 58 LINE 42

CONSERVATION DIV  
Wichita, Kansas