

KANSAS

12

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Oasis Petroleum Inc.

Complete Address 800 Sutton Place Wichita, Ks

Lease Name Coon Well No. 1

Location SW/SE/NE Sec. 35 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4243

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 2:00 PM Day 21 Month 8 Year 1970

The above well was plugged as follows:

211 ft of 8 5/8 surface pipe circulated. 4242 ft of 5 1/2 long string
cemented with 150 sacks. Top perf. 4108 ft. Sand back to 4075 ft.,
5 sacks cement with bailer. Pulled 3290 ft of 5 1/2. Set 10 ft rock
bridge at 225 ft. Fill hole with 3 1/2 yds redimix to base of cellar.

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well plugged as herein stated.

CONSERVATION DIVISION
Wichita, Kansas

Signed: D. Russell Bihentun
Well Plugging Supervisor

INVOICED

DATE 8/24/70

INV. NO. 2439-W