

Form CP-3  
Rev. 6-26-62


**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
 STATE CORPORATION COMMISSION

NOV 14 1966

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assitant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Inscho-Jackson Well No. # 2

Location SE SW NE Sec. 35 Twp. 29 Rge. 7 (E) (W)

County Kingman Total Depth 4196'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Flint Engineering and Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 2:30PM Day 8th Month Nov. Year 1966

The Above well was plugged as follows:

240' of 8 5/8" surface pipe, cemented with 165 sacks. 4195' of 5 1/2" long  
string, cemented with 100 sacks. Top perferation 4131'. Bottom of the  
hole was sanded to 4100', and cemented with 5 sacks. 3320' of 5 1/2" long  
string was recovered from the hole. Hole was filled with mud to 240',  
rock bridge from 240' to 230', and cemented with 25 sacks. Hole was  
filled with mud to 40', rock bridge from 40' to 30', and cemented with  
10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
 Well Plugging Supervisor

DATE 11/15/66

INV. NO. 4264-11