

K KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

8-24-62 AUG 21 1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Co.

Complete Address: 705 Fourth Natl Bldg. Wichita, Kansas

Lease Name ***** Inscho-Jackson Well No. 1

Location NE NE NW Sec. 35 Twp. 29 Rge. 7 (E) (W) X

County Kingman Total Depth 4241'

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221 Gt. Bend, Kansas License No. 49

Operation Completed: Hour 7 PM Day 21 Month Aug. Year 1962

The Above well was plugged as follows:

4237' of 5-1/2" pipe plugged back to 4166' with 90 sacks cement circulated.
Perforated at 4124'. Sanded back to 4100' and 5 sacks cement. 240' of
8-5/8" surface pipe circulated with 100 sacks cement. Hole filled to
200' with mud, 10' rock bridge and 20 sacks cement. Hole filled to 40'
with mud, 10' rock bridge and 10 sacks cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Herman Justus
Well Plugging Supervisor

DATE 8/28/62

INV. NO. 3549-W