

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 2 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name High Plains Production Company

Complete Address: 300 Insurance Bldg., Wichita, Kansas

Lease Name Handkins Well No. # 1

Location SE SW NW Sec. 34 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4234

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Gabbert-Jones Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No.     

Operation Completed: Hour 2:00PM Day 1st Month Nov. Year 1964

The Above well was plugged as follows:

203' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole was  
filled with drilling mud to 210', 1st cementing plug, bridged solid with  
wood and hulls on fluid at 210', and cemented with 25 sacks. Hole was  
filled with drilling mud to 40', 2nd cementing plug, bridged solid with  
dry cement and hulls on fluid at 40', and cemented with 10 sacks to the  
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 11/2/64

INV. NO. 90-W