

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION

FEB 28 1966

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name O. A. Sutton

Complete Address: 407 Insurance Bldg., Wichita, Kansas

Lease Name Handkins Well No. # 2

Location NE NE NW Sec. 34 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4162'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 2:30PM Day 25th Month Feb. Year 1966

The Above well was plugged as follows:

260' of 8 5/8" surface pipe, cement circulated. 4156' of 5 1/2" long string,  
cemented with 50 sacks. Plug back TD 4150'. Top perferation 4131'. Bottom  
of the hole was sanded to 4100', and cemented with 5 sacks. 3470' of 5 1/2"  
long string was recovered from the hole. Hole was filled with mud to 250',  
rock bridge from 250' to 240', and hole was filled with 3 1/2 yards of ready-  
mix cement from 240' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 3/1/66

INV. NO. 2784-W

Signed: Archie Elving  
Well Plugging Supervisor