

15-095-00528-0000

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued August 21, 1967.

Operator's Full Name O. A. Sutton

Complete Address: 800 Sutton Place, Wichita, Kansas 67202

Lease Name Handkins Well No. # 4

Location NW NW NW Sec. 34 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4227'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 10:30AM Day 30th Month August Year 1967

The Above well was plugged as follows:

274' of 8 5/8" surface pipe, cement circulated. 4226' of 5 1/2" long string,
cemented with 200 sacks. Top perforation 4151'. 10 sacks of cement was pumped
on bottom, with the top of the cement at 4100'. 3026' of 5 1/2" long string was
recovered from the hole. Hole was filled with mud to 270', rock bridge from
270' to 260', and cemented with 25 sacks. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks, with cement from
30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Ebling
Well Plugging Supervisor

INVOICED

DATE 9/6/67

INV. NO. 6262-W