

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sunray DX Oil Company

Complete Address: 300 Union National Bldg., Wichita, Kansas

Lease Name M. Wallace Well No. # 1

Location E/2 NE Sec. 34 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4150'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:00 PM Day 27th Month May Year 1965

The Above well was plugged as follows:

298' of 8 5/8" surface pipe, cement circulated..4150' of 5 1/2" long
string, cemented with 150 sacks. Plug back to 4146'. Top perferation
4114'. Bottom of the hole was sanded to 4100', and cemented with 5
sacks. 3140' of 5 1/2" long string was recovered from the hole. Hole was
filled with mud to 250', and 10' of rock bridge, and cemented with 25
sacks. Hole was filled with mud to 40', and 10' of rock bridge, and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/28/65
INV. NO. 1124-W