

KANSAS

W

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued August 21, 1967.

Operator's Full Name O. A. Sutton

Complete Address: 800 Sutton Place, Wichita, Kansas 67202

Lease Name Handkins Well No. # 1

Location NE NW NW Sec. 34 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4209'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 3:00PM Day 28th Month August Year 1967

The Above well was plugged as follows:

274' of 8 5/8" surface pipe, cement circulated. 4144' of 5 1/2" long string, no record of cement. This is an open hole. 10 sacks of cement was pumped on bottom, with the top of the cement at 4100'. 3790' of 5 1/2" long string was recovered from the hole. Hole was filled with mud to 270', rock bridge from 270' to 260', and cemented with 25 sacks, with cement from 260' to 185'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 9/6/67
INV. NO. 6261-4