

State of Kansas



FORM - CP-2  
Rev. 9-8-64

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

DEC 20 1965

15-007-30197-0060

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Vaughn Francis of Stickle Drilling Company has this date requested permission to plug the following described well:

Mr. Francis guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil Company

Complete Address: 300 Union National Bldg., Wichita, Kansas

Lease Name: Ernest McGuire Well No. # 1

Location: C NE NW Sec. 22 Twp. 31 Rge. 13 (E) (W) W

County Barber Total Depth 3810' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Francis was instructed to plug the well as follows:

288' of 13 3/8" surface pipe, cement circulated with 300 sacks.  
Fill hole with drilling mud to 275', 1st cementing plug, bridge  
with hulls, and cement with 50 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cement with 30  
sacks to base of cellar. Bridge and cement rat and mouse holes with  
5 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent