

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 2 - 1966

CONSERVATION DIVISION  
Wichita, Kansas

15-007-30232-0000

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Frank Pfannenstiel of Leben Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling, Inc.

Complete Address: 815 Wichita Plaza, Wichita, Kansas

Lease Name: Smith Well No. # 1

Location: C SW NW Sec. 22 Twp. 37 Rge. 13 (E)(W)W

County Barber Total Depth 3830' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

303' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill hole with drilling mud to 280', 1st cementing plug, bridge with 1/4 sack of hulls and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent