



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen' Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC -1 1965

CONSERVATION DIVISION
Wichita, Kansas

15-007-30144-0000

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Claude Boman of Tom-Kat, Inc. has this

date requested permission to plug the following described well:

Mr. Boman guarantees payment of the plugging fee.

Operator's full Name: Tom-Kat, Inc.

Complete Address: 1137 Wichita Plaza, Wichita, Kansas

Lease Name: Olson Well No. # 1

Location: C NW NE Sec. 5 Twp. 31 Rge. 12 (E)(W) W

County Barber Total Depth 3825' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Boman was instructed to plug the well as follows:

217' of 8 5/8" surface pipe, cement circulated with 150 sacks.
Fill hole with drilling mud to 210', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Ewing
Conservation Division Agent