



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

## VERBAL PERMIT FORM

(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 21 1962

CONSERVATION DIVISION  
 Wichita, Kansas

15-067-0496-0026

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

I have this date Sept 14, 1962., 1962, authorized  
 the following plugging operation:

Operator's full Name: Sunray DX Oil Company.Complete Address: 321 West Douglas, Wichita 2, Kansas.Lease Name: #1 Smith "A" Well No. #7Location: C SW SW Sec. 15 Twp. 31 Rge. 13 (E) (W)County Barber Total Depth 4700'Oil Well  Gas Well  Input Well  SWD Well  D & A 

Other well as hereafter indicated: \_\_\_\_\_

Operator was instructed to plug well as follows:

289' of 13 3/8" surface pipe circulated with 300 sacks  
cement. Hole filled to 250' with heavy drilling mud, 1/2  
sack# hulls, 1st cementing plug and 25 sacks cement. Hole  
filled to 30' with heavy drilling mud, 1/2 sack hulls, 2nd  
cementing plug and 25 sacks cement to base of cellar.  
Rat hole bridged and 2 sacks cement. Very truly yours,

*Harmon Justus*  
 Conservation Division Agent