



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-033-10030-0000

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dec 14, 1962

DEC 27 1962
 12-27-62
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Ray Richardson of Southwest Caseing Pulling Co. this

date requested permission to plug the following described well:

Mr. Ray Richardson guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway Great Bend, Kansas.

Lease Name: McMillen #1 Well No. #1


Location: C-NW- Sec. 7 Twp. 31 Rge. 16 (E) (W) X

County Comanche County Total Depth 4979' Oil Well X
Abandoned

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ray Richardson was instructed to plug the well as follows:

4978' of 4 1/2" oil string sanded to 4910' & 3 sacks cement.
4635' of 4 1/2" pipe pulled. 502' of 8 5/8" surface pipe circulated
with cement. Hole filled to 300' with mud, 10' rock bridge
and 20 sacks cement. Hole filled to 40' with mud, 10' rock
bridge and 10 sacks cement to base of cellar.

Very truly yours,

 Conservation Division Agent