



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-033-20100-0000

Dear Sir:

Mr. Freeman of Garvey Drlg. Co. has this date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.

Operator's full Name: Ferguson Oil Co. Inc. & Lee Banks

Complete Address: 725 Union Center Wichita, Ks

Lease Name: Proctor Well No. 1

Location: S/C NE Sec. 25 Twp. 31S Rge. 19 (E)(W) W

County: Gomanche Total Depth 5212 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Freeman was instructed to plug the well as follows:
456 ft 8 5/8 surface pipe cemented with 400 sacks. Pump
30 sacks cement to 700 ft. 2nd plug at 400 ft, 30 sacks
cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement
to surface. 2 sacks cement in rat hole. 2 sacks cement in
mouse hole.

Pumped by Halliburton Cementing Co., Great Bend, Ks

L. Russell Biberstein
Conservation Division Agent