



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

15-007-1915-00-01

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1962
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date 7-21-1962, 1961, authorized the following plugging operation:

Operator's full Name: Crescent Oil & Gas Corp.

Complete Address: Box 485 Ellinwood, Kansas

Lease Name: Rosie Kinsey Well No. 1

Location: SE SE NW Sec. 7 Twp. 3E Rge. 13 (E)(W) X

County: Barber Total Depth: 4665'

Oil Well Gas Well Input Well SWD Well

D & A X Other well as hereafter indicated:

Washdown

Operator was instructed to plug well as follows:

350' of 13-3/8" pipe. Hole filled with heavy drilling mud to 300'
1/2 sack hulls, 1st cementing plug and 25 sacks cement through
drill pipe. Hole filled to 30' with heavy drilling mud, 1/2 sack
hulls, 2nd cementing plug and 10 sacks cement to bottom of cellar.
Rathole bridged and 2 sacks cement.

Very truly yours,

Herman Justus

