



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 13 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-007-30230-0000

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Wayne Dobbs of Vaughan Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Inc.

Complete Address: Box 797, Great Bend, Kansas

Lease Name: Maddix "B" Well No. # 1

Location: Approx. C N/2 Sec. 12 Twp. 31 Rge. 13 (E)(W) W

County Barber Total Depth 3690' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dobbs was instructed to plug the well as follows:

205' of 8 5/8" surface pipe, cement circulated with 150 sacks.
Fill hole with drilling mud to 200', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent