

19
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

AUG 3 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa, Tulsa, Oklahoma

Lease Name Adelhardt Well No. # 1

Location C SW SE Sec. 28 Twp. 29 Rge. 10 (E) (W)W

County Kingman Total Depth 4689

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Graybol Oil Corporation

Address: 2200 National Bank of Tulsa, Tulsa, Okla. License No.

Operation Completed: Hour 5:30AM Day 30th Month July Year 1964

The Above well was plugged as follows:

256' of 8 5/8" surface pipe, cemented with 175 sacks. Hole was filled
with drilling mud to 250', 1st cementing plug, bridged solid with hulls,
on fluid at 250', and cemented with 25 sacks. Hole was filled with
drilling mud to 40', 2nd cementing plug, bridged solid with hulls, on
fluid at 40', and cemented with 10 sacks to base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 8/3/64
INV. NO. 9594-W

Signed: Archie Elving
Well Plugging Supervisor