

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

Authority Dec 30, 1982
API Number 15- -

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name TXO Production Corporation

Complete Address 200 W. Douglas, Wichita Kansas

Lease Name Eckas Well No. 1

Location C. Sw. NE. Sec. 35 Twp. 29 Rge. 43 (East)(West)

County Stanton Total Depth 5664

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargents Casing Pulling

Address Liberal Kansas License No. 511

Operation Completed: Hour: 4:00 PM Day: 25 Month: Feb Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There was 1522' of 8 1/8" surface casing, c.c. 4 1/2" casing set to 5664'. Cast Iron bridge plug at 4000 with 20 lbs cement. Perforations were 4070-4075'. 1st plug on bottom with 20 lbs cement 1 1/2" puller. 2nd plug at 1500' with 40 lbs cement. 3rd plug at 600' with 25 lbs cement. 4th plug at 40'-0" with 10 lbs cement.

There was 2712' of 4 1/2" salvaged

Amount of Surface Casing: 1522' of 8 1/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature] Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: _____ Conservation Division Agent

INVOICED

DATE 3-4-82

WV. NO. 9561-W