

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 136-41

LOCATION SW SW NE

SEC. 30 TWP 29S RGE. 41W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 54-30 Lease Wade

Operator The Superior Oil Company Address Box 690, Chickasha, Oklahoma

Field Wildcat County Stanton

Total Depth 6415 Feet.

Plugging Contractor BARNES-SONS.

Plugging Contractor's License No. 9

Address Russell Kansas

(Describe briefly the manner in which the well was plugged)

Ran to 2100 feet w/open ended D.P. Halliburton cementing plug at 2100 ft. Equalized 50 sacks Portland Reg. Cement w/2% Calcium Chloride. Top of Plug located at 1995 ft. December 5, 1953. Pulled 1227 9-5/8" Casing. Pushed wood plug to 400 ft. Dumped 10 ft. rock on top of plug. Dumped 8 sacks cement on top of rock. Dumped 27 sacks cement and filled with mud. Put 15 sack plug on top. Welded steel plate on top of surface pipe.

RECEIVED
STATE CORPORATION COMMISSION

12-12-53 DEC 12 1953

CONSERVATION DIVISION

PLUGGING
FILE SEC. 30 TWP 29 RGE. 41W
BOOK PAGE 136 LINE 41

M. L. Rivers
District Conservation Agent

Date December 7, 1953