

R

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bachus Oil Company

Complete Address: 721 East Central, Wichita, Kansas

Lease Name Heibsch Well No. # 1

Location NE NE NW Sec. 32 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 2411

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 10:00AM Day 13th Month August Year 1964

The Above well was plugged as follows:

385' of 8 5/8" surface pipe, cement circulated. 2411' of 4 1/2" long string,
cemented with the top at 1977'; Top perforation 2367'. Bottom of the hole
was sanded to 2350', and cemented with 3 sacks. Hole was filled with mud
to 300'. Plug was set at 300', with 20' of rock bridge, and cemented with
25 sacks. Hole was filled with mud to 40', with 10' of rock bridge, and
cemented with 10 sacks to the base of the cellar.
1970' of 4 1/2" long string was recovered from the hole.

INVOICED I hereby certify that the above well was plugged as herein stated.

DATE 8-18-64

INV. NO. 9655-W

Signed: Archie Elving
Well Plugging Supervisor