

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION

FEB 8 1963

CONSERVATION I.
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morgenstern and Spector Inc.

Complete Address: P. O. Box 661, Russell, Kansas

Lease Name Hiebach Well No. # 1

Location NE NE NW Sec. 32 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4434

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: Oil well never produced

Plugging Contractor: Knight Casing Pulling Co.

Address: P. O. Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 4 PM Day 4th Month Feb. Year 1963

The Above well was plugged as follows:

4461' of 5 1/2" long string cemented with 150 sacks. Plugged back to 4420'.
Top of perferation 4401'. Sanded to 3990'. 387' of 8 5/8" surface pipe
circulated with cement. Hole was filled with mud to 200'. 10' rock bridge
cemented with 20 sacks. Hole filled to 40'. 10' rock bridge cemented with
10 sacks to base cellar.

3500' of 5 1/2" pipe recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2-8-63

INV. NO. 6544-W