

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

FEB 18 1963

CONSERVATION L. P.
Wichita, KansasOperator's Full Name Morgenstern and Spector Inc.Complete Address: P. O. Box 661, Russell, KansasLease Name Goetz Well No. # 2Location NE NW NW Sec. 32 Twp. 29 Rge. 9 (E) (W) WCounty Kingman Total Depth 4437Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co.Address: P. O. Box 304, Chase, Kansas License No. 436Operation Completed: Hour 4:PM Day 13th Month Feb. Year 1963

The Above well was plugged as follows:

4437' of 5 1/2" long string cemented with 150 sacks. Plugged back to 4398'Top of perforation 4370'. Sanded to 4360' cemented with 5 sacks. 408'of 8 5/8" surface pipe circulated with cement. 134 sacks of drilling mudwas pumped in the hole to kill the gas. Hole was filled to 200' with mud,10' rock bridge was cemented with 20 sacks. Hole was filled to 40' withmud, 10' rock bridge, cemented with 10 sacks to the base of the cellar.2900' of 5 1/2" pipe recovered from the hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elwing
Well Plugging SupervisorDATE 2/18/63INV. NO. 6594-W