

40 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 29 1963

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Morgenstern and Spector

Complete Address: P. O. Box 661, Russell, Kansas

Lease Name Heibsch Well No. # 2

Location NE SW NW Sec. 32 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4433

Abandoned Oil Well      Gas Well x Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Co.

Address: P. O. Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 4:00PM Day 26th Month Jan. Year 1963

The Above well was plugged as follows:

398' of 8 5/8" surface pipe circulated with cement. 4433' of 5 1/2" long  
string cemented with 150 sacks. Plugged back to 4206'. Top of perfor-  
ation 4156'. Hole sanded to 4140' cemented with 5 sacks. Filled hole  
to 200' and 10' rock bridge cemented with 20 sacks.. Filled hole to 40'  
and 10' rock bridge cemented with 10 sacks to base cellar.  
3485' of 5 1/8" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/29/63

INV. NO. 6489-W

Signed: Audria Elving  
Well Plugging Supervisor