

15-095-00259-0000

Form CP-3  
Rev. 6-26-62

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUL 13 1964  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: R. R. # 2, Great Bend, Kansas

Lease Name Bohrer "B" Well No. # 1

Location NE NE SE Sec. 33 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4480

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 4:30PM Day 10th Month July Year 1964

The Above well was plugged as follows:  
282' of 8 5/8" surface pipe, cemented with 200 sacks. 4300' of 4 1/2" long  
string, cemented with 75 sacks. Plug back to 4189'. Top perforation 4172'.  
Bottom of the hole was sanded to 4160', and cemented with 3 sacks. Hole  
was filled with mud to 300', bridged with 10' of rock at 300', and cement-  
ed with 25 sacks, bringing the top of the cement to 235' in the surface  
pipe. Hole was filled with mud to 40', bridged with 10' of rock at 40',  
and cemented with 10 sacks to base of the cellar.  
3910' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 7/13/64  
INV. NO. 9461-w

Signed: Archie Elving  
Well Plugging Supervisor