

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 1 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Frank J. Black

Complete Address: Box 150, McPherson, Kansas

Lease Name Leslie Well No. # 3

Location NE SE SE Sec. 30 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4475

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 4:00PM Day 28th Month March Year 1963

The Above well was plugged as follows:

368' of 8 5/8" surface pipe circulated with cement. 4475' of 5 1/2" long  
string cemented with 150 sacks. Top perforation 4400'. Sanded to 4390'  
cemented with 5 sacks. Hole filled to 200' with mud, 10' rock bridge,  
cemented with 20 sacks. Hole filled to 40' with mud, 10' rock bridge,  
cemented with 10 sacks cement to base cellar.  
3520' of 5 1/2" pipe recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/1/63

INV. NO. 6802-W

Signed: Audie Elving  
Well Plugging Supervisor