

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 21 1963
1-21-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morgenstern Spector

Complete Address: P. O. Box 661, Russell, Kansas

Lease Name Leslie Well No. # 1

Location C NE SE Sec. 30 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4522

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling

Address: P. O. Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 5 PM Day 17th Month Jan. Year 1963

The Above well was plugged as follows:

4518' of long string cemented with 150 sacks, plugged back to 4242',

Top of perferation 4189', hole sanded to 4175' and 5 sacks cement.

408' of 8 5/8 " surface pipe circulated with cement. hole filled with

mud to 200', 10' rock bridge cemented with 20 sacks. hole filled with

mud to 40', 10' rock bridge cemented with 10 sacks to base cellar

3248' of pipe was recovered from the hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 1/21/63
INV. NO. 6454-W