

J
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed January 8, 1968.

Operator's Full Name Barbara Oil Company

Complete Address: 509 Union Center Bldg., Wichita, Kansas 67202

Lease Name Schulte Well No. # 1

Location C NE NW Sec. 22 Twp. 29 Rge. 10 (E) (W)

County Kingman Total Depth 4650'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gabbart-Jones, Inc.

Address: 830 Sutton Place, Wichita, Kansas 67202 License No.

Operation Completed: Hour 12:15PM Day 24th Month January Year 1968

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cement circulated with 185 sacks. Hole was
filled with drilling mud to 240', 1st cementing plug, bridged with 2 sacks
of dry cement and 1/2 sack of hulls on fluid at 240', and cemented with 26
sacks, with cement from 230' to 146'. Hole was filled with drilling mud
to 40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack
of hulls on fluid at 40', and cemented with 9 sacks, with cement from 30'
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/26/68

INV. NO. 7145-W