

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 4 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued November 20, 1967.

Operator's Full Name Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa Bldg., Tulsa, Oklahoma 74103

Lease Name Thieme Well No. # 1

Location C SW SW Sec. 22 Twp. 29 Rge. 10 (E) (W) W

County Kingman Total Depth 4680'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 1:45AM Day 3rd Month December Year 1967

The Above well was plugged as follows:

214' of 8 5/8" surface pipe, cemented with 150 sacks. 4632' of 5 1/2" long string,
cemented with 75 sacks. Plug back T.D. 4606'. Top perforation 4577'. Bottom of
the hole was sanded to 4550', and cemented with 5 sacks, through the dump
bailer, with cement from 4550' to 4510'. 1840' of 5 1/2" long string was recovered
from the hole. Fluid in the hole was bailed down to 210', bridge plug and rock
bridge from 210' to 200', and cemented with 25 sacks, with cement from 200' to
125'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elwing
Well Plugging Supervisor

INVOICED

DATE 12/5/67
INV. NO. 6831-W