

R

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued June 19, 1967.

Operator's Full Name Mull Drilling Company, Inc.

Complete Address 1625 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name Towner-Wells Well No. # 1

Location NE SE NW Sec. 18 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4184'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling, Inc.

Address Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 5:45 P.M. Day 8th Month July Year 1967

The above well was plugged as follows:

222' of 8 5/8" surface pipe, cemented with 160 sacks. 4164' of 4 1/2" long
string, cemented with 125 sacks. This is an open hole. Bottom of the hole
was sanded to 4100', and cemented with 4 sacks, through the dump bailer.
2100' of 4 1/2" long string was recovered from the hole. Hole was filled with
mud to 220', rock bridge from 220' to 210', and cemented with 25 sacks.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7-10-67

INV. NO. 5537-W