

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION
SEP 25 1964
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Petroleum Inc.Complete Address: 352 North Broadway, Wichita, KansasLease Name Legg Well No. # 2Location NE NE SE Sec. 16 Twp. 30 Rge. 7 (E) (W) WCounty Kingman Total Depth 3161Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Garvey Drilling CompanyAddress: Route 2, Great Bend, Kansas License No. Operation Completed: Hour 9:30AM Day 24th Month Sept. Year 1964

The Above well was plugged as follows:

255' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole
was filled with drilling mud to 265', 1st cementing plug, bridged with
hulls, on fluid at 265', and cemented with 25 sacks, bringing the top
of the cement to 224' in the surface pipe. Hole was filled with drill-
ing mud to 40', 2nd cementing plug, bridged solid with hulls, on fluid
at 40', and cemented with 10 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/28/64INV. NO. 9865-WSigned: Archie Elving
Well Plugging Supervisor