

Form CP-3
Rev. 6-26-62

40
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: Route 2, Great Bend, Kansas

Lease Name Legg Well No. # 1

Location NW NE SW Sec. 16 Twp. 30 Rgs. 7 (E) (W) W

County Kingman Total Depth 4303

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Co.

Address: Route 2, Great Bend, Kansas License No.

Operation Completed: Hour 10:15 PM Day 27th Month Nov. Year 1963

The Above well was plugged as follows:

290' of 8 5/8" surface pipe, cemented with 225 sacks. Hole was over fill-
ed with fluid. 1st cementing plug and 1/4 sack hulls was pushed to 275',
cemented with 25 sacks, through the drill pipe. Hole was filled with
drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack hulls,
cemented with 10 sacks to base cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/3/63

INV. NO. 8205-W