

 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CONSERVATION COMMISSION
JAN 23 1967
CONSERVATION DIVISION
KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued January 5. 1967

Operator's Full Name Phillips Petroleum Company

Complete Address: Box 287, Great Bend, Kansas

Lease Name Sinnett Well No. # 2

Location C NW SW Sec. 15 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4162'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 4:30PM Day 21st Month Jan. Year 1967

The Above well was plugged as follows:

242' of 8 5/8" surface pipe, cemented with 175 sacks. 4162' of 4 1/2" long
string, cemented with 160 sacks. Plug back T.D. 4151'. Top perferation
4130'. Bottom of the hole was sanded to 4100', and cemented with 3 sacks,
through the dump bailer. 3506' of 4 1/2" long string was recovered from the
hole. Hole was filled with mud to 240', rock bridge from 240' to 230',
and cemented with 25 sacks. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/23/67
INV. NO. 4651-W

Signed: Archie Elving
Well Plugging Supervisor