

DISTRICT CONSERVATION AGENT'S REPORT

R
~~15-173 00325 0000~~

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 89-10

LOCATION W $\frac{1}{2}$ SW SW

SEC. 5 TWP. 28 RGE. 1W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease T. A. Schmitz

Operator Eckland Drilling Company Address 218 Bissantz Bldg.
Wichita, Kansas

Field _____ County Sedgwick

Total Depth 3370 Feet.

(Describe briefly the manner in which the well was plugged)

Filled hole with chat to 3370'

Ran 5 sacks cement from 3370' to 3335'

Filled with mud to 160'

Bridge solid with rock from 160' to 150'

Ran 10 sacks cement 150' to 120'

Filled with mud 120' to 15'

Capped with 5 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL - 9 1951
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 5 T 28 R 1W
BOOK PAGE 89 LINE 60

W. O. Pien

District Conservation Agent
Date 6-26-51