

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 23 1962 11-26-62

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Nov. 16, 1962.

Dear Sir:

Mr. C. V. Burton of Pickrell Drilling Co. has this date requested permission to plug the following described well:

Mr. C. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Kansas

Lease Name: Messenger- Stapley #1 Well No. #1

Location: NE-NE-NW Sec. 19 Twp. 29 Rge. 7 (E) (W)

County Kingman Total Depth 4205' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. C. V. Burton was instructed to plug the well as follows:

224' of 8 5/8" surface pipe circulated with 160 sacks cement
Hole filled to 180' with mud, 1/2 sacks hulls, 1st cementing
plug and 20 sacks cement. Hole filled to 40' with mud, 1/2
sack hulls, 2nd cementing plug and 10 sacks cement. Rat
hole bridged and 2 sacks cement.

Very truly yours,

Herbert J. Justice
 Conservation Division Agent