

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed January 8, 1968.

Dear Sir:

Mr. A. E. Bowman of Barbara Oil Company has this
date requested permission to plug the following described well:

Mr. Bowman guarantees payment of the plugging fee.

Operator's full Name: Barbara Oil Company

Complete Address: 509 Union Center Bldg., Wichita, Kansas 67202

Lease Name: Schulte Well No. # 1

Location: N NE NW Sec. 22 Twp. 29 Rge. 10 (E)(W) W

County Kingman Total Depth 4650' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bowman was instructed to plug the well as follows:

250' of 8 5/8" surface pipe, cement circulated with 185 sacks. Fill hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent