

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

RECEIVED  
 STATE CORPORATION COMMISSION

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

DEC 2 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Sam Stevens of Garvey Drilling Co. has this

date requested permission to plug the following described well:

Mr. Stevens guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: Route 2, Great Bend, Kansas

Lease Name: Legg Well No. # 1

Location: NW NE SW Sec. 16 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4303 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Stevens was instructed to plug the well as follows:

290' of 8 5/8" surface pipe, cemented with 225 sacks.

Fill hole with drilling mud to 275', 1st cementing plug,

1/4 sack hulls, cement with 25 sacks. Fill hole with drill-

ing mud to 40', 2nd cementing plug, 1/4 sack hulls, cement

with 10 sacks to base cellar. Bridge and cement rat hole

with 2 sacks.

Very truly yours,

Aukie Elving  
 Conservation Division Agent