

15-095-01002-0000

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 3 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Stubblefield of Graybol Oil Corporation has this date requested permission to plug the following described well:

Mr. Stubblefield guarantees payment of the plugging fee.

Operator's full Name: Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa, Tulsa, Okla.

Lease Name: Adelhardt Well No. # 1

Location: C SW SE Sec. 28 Twp. 29 Rge. 10 (E) (W) W

County Kingman Total Depth 4689 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stubblefield was instructed to plug the well as follows:

256' of 8 5/8" surface pipe, cemented with 175 sacks. Fill hole with drilling mud to 250', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent