

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION

API Number 15-057

JUN 22 1982
20 25 4-0000
CONSERVATION DIVISION
Wichita, Kansas

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Richard Drilling Co.

Complete Address 110 N. Market, Suite 205, Wichita, Kansas 67202

Lease Name Ford Well No. "A" 1

Location SW-SW-SW Sec. 19 Twp. 29 Rge. 24 (East)(West)

County Ford Total Depth 5450'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated This well was equipt but never produced.

Plugging Contractor Kelco Casing Pulling

Address Box 176 Chase, Kansas 67524 License No. 618

Operation Completed: Hour: 5:20 PM Day: 17 Month: June Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They ran and cemented 5430' of 4 1/2" production pipe with 150 lbs of cement. The plug back on the 4 1/2" was at 5381'. The perforations were from 5290' to 73'. 1st plug sand off bottom back to 5240' + dumped 4 bbls of cement on sand with bailer. 2nd plug pumped through 8 5/8" with 5 bbls bulls 25 bbls Jell's release rubber plug + follow it with 150 lbs of cement. They recovered 2818' of 4 1/2" production pipe. The plugging was accomplished by Halaburton Co. The cement used was 50/150 grade with 2% Jell 3% c.c.
Amount of Surface Casing: 50' of 8 5/8" cement circulated with 300 lbs cement.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luther
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED
DATE 6-24-82
INV. NO. 180-u