

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Amaco Production Company

Complete Address Box 432, Liberal, Kansas

Lease Name Rohmeyer Operating Well No. 1

Location App C NE NW Sec. 30 Twp. 29 Rge. 32 (E) (W)

County Haskell Total Depth 5800'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 12 Month 7 Year 1972

The above well was plugged as follows:

8 5/8" to 792' circulated w/ cement. 5 1/2" 5514' cemented.

Top perforations 5302' Plug bottom w/ Bridge plug & 5 sacks cement.

Top of cement 4560' Mud 4560' to 2600'

Spotted 30 sacks cement 2600' to 2500' Mud 2500' to 1200'

Spotted 30 sacks cement 1200' to 1100' Mud 1100' to 850'

Spotted 30 sacks cement 850' to 750' Mud 750' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'. Company Pump

Pulled 1415' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *[Signature]*
Well Plugging Supervisor

DATE 7/17/72
INV. NO. 6035-W