

*HP*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

APR 1 1963

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Robert F. White

Complete Address: 714 Union Center Wichita, Kansas

Lease Name Collingwood Well No. # 1

Location C NW NE Sec. 8 Twp. 29 Rge. 34 (E) (W)

County Haskell Total Depth 5649'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling Co. Inc.

Address: Great Bend, Kansas License No. 399

Operation Completed: Hour 5 PM Day 26 Month 3 Year 63

The Above well was plugged as follows:

8 5/8" 1800' Circulated w/cement. 5 1/2" 5649' Cemented.

Perforations 5445' to 4578' Sand 5649' to 4500'

5 Sax.cement 4500' to 4450' Mud 4450' to 710'

10' Rock Bridge 710' to 700' 35 Sax.cement 700' to 600''

Mud 600' to 50' 10' Rock Bridge 50' to 40'

15 Sax.cement 40' to surface. Pulled 2010' 5 1/2" Pipe. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Hugh Dent*  
Well Plugging Supervisor

DATE 4/1/63

INV. NO. 6800-W